

ADDENDUM NUMBER [2]

Adams Street Lift Station Improvements

BID DATE: April 28, 2009

This Addendum forms a part of the Bidding Documents and modifies the original Project Manual and drawings for the **Adams Street Lift Station Improvements**. Receipt of this Addendum must be acknowledged in the space provided on the Bid Form at the time that the Bid is submitted. Failure to do so may subject the Bidder to disqualification.

The following changes are hereby made to the Contract Documents:

Specifications:

1. Section 01400 Quality Control
 - 1.3. Tests and Inspections: Change paragraph A to read: The Contractor will employ and pay for the services of a qualified, independent testing laboratory to conduct the tests to determine compliance with the specifications for the following:
2. Section 01500 Construction Facilities and Temporary Controls
 - 1.1 Working Hours. Change the first sentence to read: "Conduct all construction activities between the hours of 7:00 a.m. and 7:00 p.m., Monday through Friday, except for emergencies."
3. Section 01010 Summary of Work
 - C. Work Sequence, sub-paragraph 4. Change the second sentence to read: "Provide temporary alarms (consisting of a high water alarm, pump fail to run alarm, and emergency power alarm), sewage pump, and emergency power equipment backups as necessary to prevent sewage backups or sewage spills.
4. Bid Form: Paragraph 2. Change the second sentence to read: "This Bid will remain subject to acceptance for forty-five (45) days after the day of the Bid opening."
5. Construction Contract: For clarification. Disregard the reference to the \$300.00 Liquidated Damages for Final Payment made during the pre-bid meeting and noted in the pre-bid minutes. Construction Contract shall remain as provided in the Contract Documents.
6. Section 02486 Seeding
 - 2.1. Fertilizer, sub-paragraph A. Commercial Product 1.a.1) Change to: "Nitrogen (N) is twenty pounds per acre (20 lbs/acre)."
 - 2.3. Mulch, sub-paragraph A.: Change to read: "Certified Noxious Weed Free Native Grass Hay. Hay that includes brome, timothy, orchard, crested wheat, pubescent wheat or intermediate wheat grass or similar is not acceptable."
 - 3.7 Fertilizing, sub-paragraph A.1.: Change to read: "Apply at a rate of twenty pounds per acre (20 lbs/acre), Nitrogen (N) or as recommended by seed supplier for optimal growth in Laramie, WY."

7. Section 02513 Pavement Repair and Resurfacing
2.1 Materials, sub paragraph B.1 Base Course: Change to read: Reference "Standard Specifications" Table 803.4.4-1 Grading "GR", eleven inches (11") thick.
8. Section 02741 Asphaltic Concrete Paving
1.3. Site Conditions: Sub paragraph A. Site Information: Change first sentence to read: The Contractor shall place eleven inches (11") of compacted Grade GR road base and shape the parking lot so that it meets the design grade.
9. Section 02615 Ductile Iron Pipe
2.7. Accessories. Add sub paragraph C. Sacrificial Anodes. Sacrificial anodes shall be 17# (seventeen pound), high potential magnesium prepackaged in a 75% (seventy-five percent) gypsum, 20% (twenty percent) Wyoming bentonite, and 5% (five percent) sodium sulfate backfill composition in a cloth bag with a minimum packaged weight of 45# (forty-five pounds). A 10-foot No. 12 AWG black insulated solid copper wire shall be attached. Dow Galvomag 17D3, Maxmag 17S3, or equivalent.
10. Section 16910 Programmable Controller (PLC) System
2.6. Antennas and Accessories: Change sub paragraph G.1.b. to read: (2) units to be installed at other City facilities. Coordinate exact location with the Owner. Owner shall make final connections between Antenna and radio. Owner shall program existing radio as required.
Locations: City of Laramie Wastewater Treatment Plant, 2778 Banner Road, Laramie, WY; City of Laramie Fire Training Facility, 2451 County Shop Road, Laramie, WY.
11. Section 16612 Standby Generator Set: Diesel
2.2. Performance: sub paragraph B.1. add the following sentence: Generator KW rating listed below shall be net delivered at the project altitude of 7,150 feet MSL.

Drawings:

1. Sheet C3. Reference the existing wetwell and lift station: Change note: cut holes two places, to read; "cut two inch (2") holes two places."
2. Sheet C3. Add the following to note 8. The Contractor shall be allowed to discharge groundwater resulting from construction dewatering on the property to the East of the project area, approximately 1,500' (one thousand five hundred feet) to the East provided the water quality is sufficient to obtain a WYPDES permit. It is believed one personal agricultural use well is South of the property.

Misc:

1. Current ground water level approximately six feet (6') below grade. (4-23-09)

APPROVED BY _____
City Project Manager

DATE _____

*** End of ADDENDUM ***