

SECTION 00 91 13

ADDENDUM

Colorado	3.
-----	-----
State	Addendum Number
Boulder	December 31, 2009
-----	-----
County	Date

Project: 2.0-MG Andrews Tank Improvements Project

Owner: Left Hand Water District

Bid Date: January 5, 2010

Bid Time: 2:00 p.m.

Location: at the offices of Left Hand Water District
6800 Nimbus Road
Longmont, Colorado 80503
(303)530-4200

Clarifications, revisions and modifications to the Documents are as follows:

Revisions to Contract Documents (Division 00):

Section 00 41 00 - Bid Schedule

Replace the existing Bid Schedule with the attached Bid Schedule. The attached Bid Schedule incorporates the changes made in Addendum No. 2 as well as the following:

Bid Item No. 17 – 12 Inch Gate Valves: Quantity changed from 2 to 3.

Added Bid Item No. 33 – Combination Air Vacuum Valves and Manhole

Revisions to General Provisions: None

Revisions to Section 0800 - Special Conditions: None

Revisions to Technical Specifications (Division 01 through Division 33):

Section 01 20 00 – Measurement and Payment

Add the following:

2.33 ITEM NO. 33 – COMBINATION AIR-VACUUM VALVES AND MANHOLE

- A. Item No. 33, Combination Air-Vacuum Valves and Manhole, measured for payment on a Lump Sum (LS) basis, includes all labor, tools and equipment to furnish and install the two 2-inch air-vacuum valves and manhole. The work includes all piping, joints, saddles, corporation stops, valves and other appurtenances associated with the installation of the air-vacuum valves. The work also includes all work, materials and labor associated with the 48-inch ID manholes including excavation, concrete grade beams, bedding, risers, flat lid, ring and cover and backfill.
- B. Payment for the Combination Air-Vacuum Valves and Manhole will be made at the Contract Lump Sum (LS) price in accordance with the Contract Documents.
- C. The drawings are referenced as being the basis for acceptance of completed work.

Acknowledgment:

Acknowledgment of receipt of this addendum shall be made on Page 2 of SECTION 00 42 00 – PROPOSAL. Failure to acknowledge receipt of this addendum may be cause for rejection of the bid.

The Contract Documents and Construction Specifications shall not be altered and/or changed in any other way than as heretofore indicated and/or specified.

Bates Engineering, Inc.

Prepared by: Christian Badger
Christian Badger, P.E.

Date: December 31, 2009

Transmitted by email to all plan holders

END OF SECTION

**Left Hand Water District
2-MG Andrews Water Storage Tank Improvements**

**SECTION 00 41 00
BID SCHEDULE**

Item No.	Description	Quan	Unit	Unit price Written in Words	Unit Price written in Figures	Total Price
1.	Mobilization & On-going Project Costs	1	LS		\$	\$
2.	Temporary Fire Protection	1	LS		\$	\$
3.	Clearing and Grubbing	1	LS		\$	\$
4.	Traffic Control	1	LS		\$	\$
5.	Site Maintenance	1	LS		\$	\$
6.	Tree Removal and Off Site Disposal	18	EA		\$	\$
7.	18" PVC Pipe Demolition	1	LS		\$	\$
8.	Erosion and Sedimentation Control	1	LS		\$	\$

**Left Hand Water District
2-MG Andrews Water Storage Tank Improvements**

Item No.	Description	Quan	Unit	Unit price Written in Words	Unit Price written in Figures	Total Price
9.	4- Foot Polypropylene Safety Grid Fence	300	LF		\$	\$
10.	Excavation	1	LS		\$	\$
11.	18-Inch DIP Inlet Pipeline, Bore and Casing	1	LS		\$	\$
12.	12-Inch DIP Outlet Pipeline, Bore and Casing	1	LS		\$	\$
13.	12-Inch DIP Overflow Pipeline, Bore and Casing	1	LS		\$	\$
14.	18-Inch C905 PVC Inlet Pipeline	45	LF		\$	\$
15.	12-Inch C900 PVC Outlet and Bypass Pipeline	300	LF		\$	\$
16.	WST 12-Inch Steel Pipe Overflow Assembly	1	LS		\$	\$
17.	12-Inch Gate Valve	3	EA		\$	\$

**Left Hand Water District
2-MG Andrews Water Storage Tank Improvements**

Item No.	Description	Quan	Unit	Unit price Written in Words	Unit Price written in Figures	Total Price
18.	18-Inch Butterfly Valve	1	EA		\$	\$
19.	Aquafin 2K/M with Joint Tape- 2000	890	LF		\$	\$
20.	Interior Access Steel Ladder and Cage	1	EA		\$	\$
21.	Crack Injection on Roof Interior	10	LF		\$	\$
22.	Remove Existing Surface Coatings on Roof Interior	200	SF		\$	\$
23.	Cementitious Surface Patching on Roof Interior	10	EA		\$	\$
24.	Cementitious Surface Patching on Roof Exterior	5	EA		\$	\$
25.	Roof Closure Placement at Existing Overflow Penetration	1	LS		\$	\$

**Left Hand Water District
2-MG Andrews Water Storage Tank Improvements**

Item No.	Description	Quan	Unit	Unit price Written in Words	Unit Price written in Figures	Total Price
26.	3'-0" X 3'-0" Foot Access Hatch, Hatch Walls and Handrail	1	LS		\$	\$
27.	WST Vent SS Insect Screen	1	LS		\$	\$
28.	Tank Cleaning and Disinfection	1	LS		\$	\$
29.	Pipelines Chlorination and Testing	1	LS		\$	\$
30.	6-Foot PVC Coated Chain Link Fence	500	LF		\$	\$
31.	Access Road	1	LS		\$	\$
32.	Site Restoration	1	LS		\$	\$
33.	Combination Air Vacuum Valves and Manhole	1	LS		\$	\$

END OF BID SCHEDULE

