



SITE BENCHMARK
 PIPE BENCHMARK
 ELEV. +497.75

COORDINATES		
POINT	NORTHING	EASTING
1	5205.05	5196.76
2	5009.05	5196.76
3	4989.53	5203.89
4	4978.53	5203.89

DUCT BANK SCHEDULE			
DUCTBANK NAME	CIRCUIT NAME	RACEWAY SIZE	ROUTING
D-1	P-PAC-1	1 1/4" C	MCC-3 TO TRUCK FILL CONTROL PANEL
	C-PAC-3	3/4" C	CP-03/04 TO PAC TRANSFER CONTROL PANEL

- NOTES:**
- ① OVERSIZE CORE DRILL CONCRETE WALL FOR CONDUITS, SEAL W/ LINK SEAL MODULAR OR APPROVED EQUAL.
 - ② TURN UP THROUGH EXISTING FLOOR BLOCK-OUT IN BLOWER ROOM.
 - ③ CORE HOLE IN FLOOR. TURN UP IN BLOWER ROOM.

