

WASTEWATER TREATMENT PLANT IMPROVEMENTS / EXPANSION PHASE 1 LIFT STATION AND HEADWORKS FACILITIES

FOR THE
CITY OF LAMAR, COLORADO

JUNE 2009

GENERAL NOTES

1. LOCATIONS OF UNDERGROUND AND OVERHEAD UTILITIES SHOWN WERE DETERMINED BY THE BEST AVAILABLE INFORMATION. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE LOCATION OF ALL EXISTING UTILITIES. CONTRACTOR SHALL REPORT TO ENGINEER ANY DISCREPANCIES WITH UTILITIES THAT HAVE AN EFFECT ON THIS PROJECT AS DESIGNED.
2. THE CONTRACTOR SHALL CONTACT THE APPROPRIATE UTILITY AGENCIES 48 HOURS PRIOR TO ANY EXCAVATION TO OBTAIN ACCURATE UTILITY LOCATIONS.
3. CONTRACTOR TO COORDINATE WORK IN PUBLIC RIGHTS-OF-WAY WITH THE APPROPRIATE CITY, COUNTY, AND LOCAL AGENCIES.
4. ALL EXISTING STRUCTURES, FENCES, AND IMPROVEMENTS DESTROYED, DAMAGED, OR REMOVED DUE TO CONSTRUCTION OF THIS PROJECT SHALL BE REPLACED OR RESTORED IN LIKE AND KIND AT CONTRACTOR'S EXPENSE, UNLESS OTHERWISE INDICATED.
5. ALL AREAS DISTURBED BY CONSTRUCTION SHALL BE RETURNED TO ORIGINAL OR BETTER CONDITION AND REVEGETATED AS REQUIRED IN THE SPECIFICATIONS.
6. SUPPORT ALL UTILITY LINES AND VALVES DURING CROSSING WITH ADEQUATE STRUCTURAL MEMBERS TO AVOID ANY MOVEMENT OF LINES.
7. SUBSURFACE SOIL INVESTIGATIONS WERE CONDUCTED AS PART OF THE DESIGN OF THIS PROJECT. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO CONDUCT ANY ADDITIONAL INVESTIGATIONS DEEMED NECESSARY. COPIES OF THE GEOTECHNICAL REPORT ARE INCLUDED IN THE CONTRACT DOCUMENTS.
8. THE SITE SURVEY WAS PROVIDED BY THE CITY OF LAMAR.
9. EXISTING SURVEY MONUMENTS WHICH ARE DISTURBED OR DAMAGED DUE TO CONSTRUCTION OF THIS PROJECT SHALL BE REPLACED BY LICENSED SURVEY USING STANDARD SURVEY TECHNIQUES AND IN ACCORDANCE WITH THE REQUIREMENTS OF THE APPROPRIATE AGENCY AT THE CONTRACTORS EXPENSE.
10. CONTACT UTILITY NOTIFICATION CENTER OF COLORADO 811 FOR UTILITY LOCATIONS. CALL TWO BUSINESS DAYS IN ADVANCE BEFORE DIGGING, GRADING OR EXCAVATION, FOR MARKING OF UNDERGROUND UTILITIES.
11. ALL CONSTRUCTION ACTIVITIES SHALL COMPLY WITH LOCAL AND STATE CODES AND REGULATIONS.
12. NO CONSTRUCTION WILL BE PERMITTED UNTIL ALL REQUIRED APPROVALS AND PERMITS ARE OBTAINED.
13. ALL UTILITIES ARE TO BE FIELD-LOCATED PRIOR TO CONSTRUCTION. REPORT ANY DISCREPANCIES TO THE DESIGN ENGINEER PRIOR TO THE START OF CONSTRUCTION.
14. CONTRACTOR TO MAINTAIN AT SITE CLEAN, DRY, LEGIBLE SET OF PLANS. RECORD INFORMATION AS CONSTRUCTION PROGRESSES. CONTRACTOR TO MAKE AVAILABLE TO DISTRICT'S REPRESENTATIVE/AGENT DURING ON-SITE VISITS THESE "MARKED-UP" PLANS.

OFFICIALS

MAYOR

NELVA HEATH

CITY COUNCIL

ROGER STAGNER
SKIP RUEDEMAN
BEVERLY HAGGARD
JIM LARRICK
P.J. WILSON
RON COOK



CALL UTILITY NOTIFICATION
CENTER OF COLORADO
811
CALL 2-BUSINESS DAYS IN
ADVANCE BEFORE YOU DIG,
GRADE, OR EXCAVATE FOR THE
MARKING OF UNDERGROUND
MEMBER UTILITIES.

SCALE VERIFICATION
0 1"
IF NOT 1 INCH ON
THIS SHEET, ADJUST
SCALES ACCORDINGLY

 **The Engineering Company**
2310 East Prospect Road, Suite B Fort Collins, CO 80525
(970) 484-7477 www.Tec-engrs.com

E:\2009 Projects\09-028.05\09028.05.dwg Plot date:5/25/2009